

NORTHERN RAILWAY ZONE - OFFICIAL INFRASTRUCTURE TENDER SUBMISSION

Tender Inviting Authority: Chief Project Manager Electrical Track, Northern Railway Headquarters, Baroda House, New Delhi - 110001

Tender Notice No.: NR/HQ/W-III/2026/7190-L

Name of Work: Scheduled Maintenance and Modernization of Station Yard Illumination and Auxiliary Power Distribution Systems along the Delhi-Ambala Railway Trunk Corridor.

SECTION 1: FINANCIAL DECLARATION AND BID SUMMARY

Estimated Value: 7500000.00

Bid Amount: 7372500.00

Calculated Bid-to-Estimate Ratio: 0.983

Earnest Money Deposit: 150000.00 deposited via RTGS UTR No NRIN202609179921 Performance Bank Guarantee Commitment: 5 percent of Quoted Amount upon Letter of Acceptance

SECTION 2: VENDOR PROFILE AND CORPORATE HISTORY

Name of Bidding Enterprise: Sterling Railway Power & Infrastructure Ltd.
Registered Office: Industrial Area Phase 2, Chandigarh - 160002

Vendor Age: 6687 Days Permanent Account Number: KLMNP9012R

GSTIN Registration Number: 04KLMNP9012R1Z1 Employee Count: 33

Corporate History and Track Record: Sterling Railway Power & Infrastructure Ltd. has operated continuously since 2008 as a certified Class-1 electrical contractor registered with Northern and Western Railway zones. Over the past 18 years, our enterprise has successfully executed 64 major electrification and yard lighting projects for national railway authorities and public sector undertakings. We maintain an accredited ISO 9001 and OHSAS 18001 quality management framework, supported by 33 permanent engineering and safety personnel.

SECTION 3: PLAN OF ACTION AND EXECUTION PHASING

The execution of the Delhi-Ambala modernization project will strictly adhere to RDSO specifications, Indian Electricity Rules, and Northern Railway safety guidelines.

Phase 1: Pre-Construction Survey and Logistics Mobilization (Weeks 1 to 4): Conducting joint joint-inspection surveys with railway engineering authorities. Staging heavy-duty galvanized structural masts, copper cabling drums, and distribution switchgear in secured railway storage yards. Scheduling mandatory traffic blocks with divisional operations controllers to ensure zero disruption to regular passenger train movements.

Phase 2: Civil Foundations and Earthing Installation (Weeks 5 to 12): Excavating foundation pits in designated railway land boundaries. Pouring M-25 grade reinforced cement concrete block footings with heavy-duty anchor bolts and template alignment. Installing copper-bonded earth rods and G.I. strip earthing networks to maintain comprehensive substation earthing resistance below 0.5 Ohms.

Phase 3: Mast Erection and Cable Laying (Weeks 13 to 20): Erecting 9-meter and 12-meter hot-dip galvanized octagonal poles using specialized truck-mounted cranes during permitted night-time power blocks. Laying armored aluminum cables through underground HDPE protective conduits along ballast shoulders. Mounting high-efficiency IP66 LED luminaires and weather-proof distribution boxes.

Phase 4: Testing, Inspection, and Commissioning (Weeks 21 to 24): Performing rigorous Megger insulation testing, loop impedance checks, high-voltage flashover testing, and lux-level photometric verifications across all platforms. Submitting complete as-built CAD wiring diagrams, NABL laboratory test certificates, and statutory safety clearance certificates prior to final commercial handover.

SECTION 4: BILL OF MATERIALS AND TECHNICAL SPECIFICATIONS

1. Galvanized Masts: 90 units of hot-dip galvanized octagonal poles conforming to IS 2713 standards with anti-corrosive industrial coating.

2. LED Luminaires: 180 units of 140W modular railway platform floodlighting fixtures with integrated surge protection $\geq 10\text{kV}$.
3. Power Cabling: 3,500 meters of 1.1 kV grade XLPE insulated armored aluminum conductor cables.
4. Distribution Switchboards: 4 units of compartmentalized outdoor feeder pillars equipped with MCCBs and digital metering.

SECTION 5: COMMERCIAL JUSTIFICATION AND COMPLIANCE Our competitive financial quotation of 7372500.00 reflects fair market pricing, standard material sourcing from approved RDSO vendors, and full statutory compliance under the Minimum Wages Act, Employees Provident Fund (EPF), and the Railways Act. All tax obligations are fully up to date, and the bid carries zero qualifications or conditional exemptions.