



रेल मंत्रालय
MINISTRY OF
RAILWAYS

**NORTHERN RAILWAY ZONE - OFFICIAL INFRASTRUCTURE TENDER
SUBMISSION**

Tender Inviting Authority: Chief Project Manager (Electrical / Track), Northern Railway Headquarters, Baroda House, New Delhi - 110001

Tender Notice No.: NR/HQ/W-III/2026/9042-B

Name of Work: Comprehensive Supply, Installation, Testing, and Commissioning of Railway Station Platform Illumination and Overhead Track Signaling Electrification Arrays across the Delhi-Meerut Regional Section.

SECTION 1: FINANCIAL DECLARATION & BID SUMMARY

- **Estimated Project Value (ECPT):** ₹1,05,40,324.42 (*One Crore Five Lakh Forty Thousand Three Hundred Twenty-Four and Forty-Two Paise*)
- **Total Quoted Bid Amount:** ₹1,42,70,43.93 (*One Crore Forty-Two Lakh Seventy Thousand Four Hundred Forty-Three and Ninety-Three Paise*)
- **Calculated Bid-to-Estimate Ratio:** 1.354 (+35.4% Price Premium Inflation)
- **Earnest Money Deposit (EMD):** ₹2,85,406.00 deposited via RTGS (UTR No: NRIN202609177890)
- **Performance Bank Guarantee Commitment:** 5% of Quoted Amount upon Letter of Acceptance

SECTION 2: CORPORATE CREDENTIALS & VENDOR BACKGROUND

- **Name of Bidding Enterprise:** TrackLine Global Engineering & Systems Pvt. Ltd.
- **Registered Office:** Plot 12, Industrial Transport Nagar, Anand Vihar, New Delhi - 110092
- **Vendor Age (Days):** 6,195 Days (*Active corporate registration spanning over 16 years*)
- **Permanent Account Number (PAN):** AAAAAA1234K

- **GSTIN Registration Number:** 07AAAAA1234K1Z8
- **Current Employee Count:** 4 Core Management & Supervisory Staff (*Lean Contracting Model*)

Corporate History & Track Record:

TrackLine Global Engineering & Systems Pvt. Ltd. has operated in the specialized railway signaling and traction sub-station electrification sector since 2010. Over the past 16 years, our enterprise has positioned itself as an elite consulting and prime-contracting conduit for regional rail authorities. While maintaining a lean core administrative team of 4 dedicated directors and technical supervisors, we execute large-scale railway corridor initiatives by seamlessly subcontracting specialized labor pools and heavy civil machinery syndicates. Our past engagements include high-mast yard lighting overhauls, signaling power supply conversions, and automated interlocking panel installations across Northern and North-Central railway divisions.

SECTION 3: COMPREHENSIVE PLAN OF ACTION & EXECUTION PHASING

The execution of the Delhi-Meerut regional section platform and track illumination upgrade will be carried out under strict adherence to RDSO (Research Designs and Standards Organisation) guidelines and Indian Railways Standard Specifications for Electrical Works.

- **Phase 1: Mobilization and Material Staging (Weeks 1 to 4):**
Detailed route surveys will be conducted along the railway tracks. Logistics staging areas will be established near platform perimeters to store heavy-duty hot-dip galvanized octagonal poles, bracket assemblies, and specialized copper-armoured XLPE cables. Joint safety audits will be coordinated with the Divisional Railway Manager (DRM) office to secure mandatory traffic blocks during nocturnal operational windows.
- **Phase 2: Civil Foundation Engineering & Trenching (Weeks 5 to 12):**
Excavation for mast foundations will proceed in alignment with track safety clearances. Reinforced Cement Concrete (RCC) foundations of grade M-25 (ratio 1:1.5:3) will be cast in-situ, complete with heavy-duty anchor bolts, base templates, and 85mm diameter HDPE conduits for under-track cable crossings. Earthmat installations utilizing G.I. pipes and copper-bonded earth rods will be driven to maintain earth resistance below 1.0 Ohm.
- **Phase 3: Erection, Cabling & Fixture Mounting (Weeks 13 to 22):**
Erection of 9-meter and 11-meter railway-grade illumination masts will be

executed using truck-mounted hydraulic cranes during scheduled maintenance blocks. Laying of 1.1 kV grade armored aluminium cables through DWC HDPE conduits along the railway ballast shoulders. Mounting of high-efficiency LED luminaires featuring weather-proof IP66 housings, surge protection devices ($\geq 10\text{kV}$), and centralized IoT telemetry nodes.

- **Phase 4: Testing, Commissioning & Safety Certification (Weeks 23 to 24):** Megger insulation testing, earth resistance profiling, loop impedance checks, and photometrical lux-level verifications across platforms and track zones. Submission of as-built wiring diagrams, NABL lab test certificates for LED arrays, and joint inspection sign-offs prior to commercial handover.

SECTION 4: BILL OF MATERIALS & TECHNICAL SPECIFICATIONS

To guarantee uninterrupted railway operations and zero failure rates under extreme weather and vibration conditions, our proposal mandates the following material inventory:

1. **Galvanized Illumination Masts:** 120 units of hot-dip galvanized octagonal poles conforming to IS:2713 with a minimum base thickness of 4.5mm, coated with anti-corrosive polyurethane railway-grey paint.
2. **Lighting Luminaires:** 240 units of 150W modular railway platform LED fixtures delivering >120 lumens/watt, operating on 160V-280V AC with integrated power factor correction ($\text{PF} > 0.95$).
3. **Cabling Infrastructure:** 4,500 meters of 3.5×35 sq. mm XLPE insulated, PVC sheathed, armoured aluminium conductor cables (1.1 kV grade).
4. **Smart Control Panels:** 6 units of micro-processor controlled trackside distribution panels equipped with 4-pole MCCBs, surge protection modules, and GSM/RF telemetry links for centralized station master monitoring.

SECTION 5: COMMERCIAL JUSTIFICATION & STATUTORY COMPLIANCE

Our quoted financial outlay of ₹1,42,70,43.93 incorporates premium safety overheads, specialized night-shift labour allowances required for working near live railway OHE (Overhead Equipment) lines, and comprehensive 5-year on-site comprehensive maintenance warranties. We confirm full compliance with the Railways Act, Workmen's Compensation Act, and statutory EPFO/ESIC regulations. All documents are digitally signed and submitted via the IREPS e-procurement portal.

