

NORTHERN RAILWAY ZONE - OFFICIAL INFRASTRUCTURE TENDER SUBMISSION

Tender Inviting Authority: Chief Project Manager Electrical Track, Northern Railway
Headquarters, Baroda House, New Delhi - 110001

Tender Notice No.: NR/HQ/W-III/2026/5521-PI

Name of Work: Comprehensive Overhaul of Railway Platform High-Mast Lighting
Systems and Substation Feeder Panels across the Ambala Cantt Division.

SECTION 1: FINANCIAL DECLARATION AND BID SUMMARY

Estimated Value: 10000000.00

Bid Amount: 14500000.00

Calculated Bid-to-Estimate Ratio: 1.450

Earnest Money Deposit: 290000.00 deposited via RTGS UTR No NRIN202609175511
Performance Bank Guarantee Commitment: 5 percent of Quoted Amount upon Letter of
Acceptance

SECTION 2: VENDOR PROFILE AND CORPORATE HISTORY

Name of Bidding Enterprise: Northern Power & Infrastructure Projects Ltd.

Registered Office: Industrial Focal Point, Ambala Cantt, Haryana - 133001

Vendor Age: 5400 Days

Permanent Account Number: PQRSW5678H

GSTIN Registration Number: 06PQRSW5678H1Z9

Employee Count: 12

Corporate History and Track Record: Northern Power & Infrastructure Projects Ltd. has
been active in electrical contracting since 2011. Our firm specializes in railway platform
lighting and yard electrification, maintaining a permanent engineering staff of 12
specialists.

SECTION 3: PLAN OF ACTION AND EXECUTION PHASING The execution of the Ambala Cantt yard project follows standard RDSO guidelines and Indian Railways electrical codes.

Phase 1: Survey and Staging (Weeks 1 to 4): Site reconnaissance and material staging.

Phase 2: Foundation Engineering (Weeks 5 to 12): Casting reinforced concrete mast foundations and installing earthing grids.

Phase 3: Erection and Cabling (Weeks 13 to 20): Erection of galvanized octagonal poles and laying of armored power cables.

Phase 4: Testing and Commissioning (Weeks 21 to 24): Insulation testing, loop checks, and statutory safety certification.

SECTION 4: BILL OF MATERIALS AND TECHNICAL SPECIFICATIONS

1. Galvanized Masts: 80 units of hot-dip galvanized octagonal lighting poles.
2. Luminaires: 160 units of 150W modular platform LED floodlights.

SECTION 5: COMMERCIAL JUSTIFICATION AND COMPLIANCE

Our financial bid of 14500000.00 covers specialized material procurement and premium logistical overheads. All statutory EPFO, ESIC, and railway regulations are fully satisfied.